



OFFICE OF THE SUPERINTENDING ENGINEER (CIVIL)
HYDEL MAINTENANCE & SURVEY INVESTIGATION
MP POWER GENERATING CO. LTD. SHAKTI BHAWAN
BLOCK NO. -1 RAMPUR , JABALPUR

No.03-03-02/Enquiry -121/ 242

Jabalpur/dated 29/02/2026

To,

"on mppgcl web site"

Sub:- Water proofing Treatment at Terrace for Central training Institute MPPGCL, Nayagaon Jabalpur.

TERMS AND CONDITIONS

1. Please submit your offer along with terms & Conditions for work of ,on or before **16/03/2026** up to 1.00 PM. The offer should be valid for 180 days from the date of opening. **"The quotation should be sealed in cover and should be prominently on the cover top due date, subject, and reference of the enquiry. The quotation on sealed envelope shall be required to be put by the bidder in sealed tender box only which is kept in this office for this purpose. The bid can only be put in the tender box during office hours till 1.00 PM on 16/03/2026. Enquiry will be opened on same day on 5.30 PM.**

2. The offer should be submitted in two envelop.

Envelop 1:- Containing PQR documents i.e.

i. EPF & GST Registration.

ii. Valid registration in "B" CLASS or above/MPPWD Single Class Registration.

Or Same/Similar nature work experience if not registered.

Envelop 2:-Price bid.

First the envelop 1 shall be opened & those who will qualified in PQR document, they are eligible for opening of envelop-2.

2. If the bidder fails to submit document in envelop 1, then offer shall be rejected & not considered in any case. Decision of MPPGCL is final and binding in this regard.

3. **PAYMENT:-** 100% payment shall be made within 45 days or in queue whichever is later after satisfactory completion of work certified by the in charge of work and there after submission of bill in triplicate to this office part payment will also be considered. MPPGCL shall not be liable for Interest due to delay in payment.

4. **TAXES & DUTIES :-**

a. **GST:-** The firm should have GST valid registration.

b. Firm shall responsible to comply all Taxation/duties and regulation as applicable at the time of submission of monthly bill.


5. **PANALTY:-** In case delay of job completion with in specified period, this office may its option shall be free to recover a penalty @ ½ % per week to the extent of 10 % for the total value of the services.
6. **WORK PLACE :-** Central training Institute MPPGCL, Nayagaon Jabalpur.
7. **WORK DETAILS:** As per attached schedule of work.
8. **INCOME TAX:** - The income tax shall be deducted by office from your bill/invoice.
9. **COMPLETION PERIOD:** - One Months (01) from date of site hand over or date of order which ever is later.
10. **ESTIMATED VALUE:-**Rs. 1,94,983.00/- Including GST.
11. **DISPUTE:-**Any dispute whatsoever shall be settle under Jabalpur court jurisdiction.
12. **MAN POWER:-** The Contractor has to deploy adequate number of workmen and supervisory staff for proper execution of work. Submit copy to the authorized representative of Er. In-Charge of "Aadhar Cards" of workmen, and ensure that minimum wages as Govt. rules & factory Act 1948.
13. **ENGINEER IN- CHAGE:-** The A.E. (Civil) HM & SI MPPGCL, Jabalpur.
14. **EPF & ECR:-** At the time of submission of bill EPF challan copy, Eletronic challan cum return (ERC) of each labour.
15. **EPF REGISTRATION & INSURANCE:-** The contractor should get engaged labour registration under EPF registration Act & get them insured. According submit the related documents for record. The MPPGCL, will not responsible for any accident/injury to the labour engaged the currency of job contract. Deposition of EPF contribution as per EPF act shall be whole responsibility of contractor.
16. **LABOUR PAYMENT:-**Labour payment must be done as per minimum wages act.
17. **COMPLIANCE OF LABOUR LAWS:-** The Contractor shall be bound by the provision of the litigation like factory act/workman compensation act and other laws of state/Central Govt. as in force, litigation of Jabalpur Court only.
18. **AGREEMENT:-** The successful tenderer will be required to execute an agreement bond, on non judicial stamp paper of Rs. One Thousand (1000/-), affixed with Revenue stamp of Rs. 2/- for proper and due to fulfillment of contract. Cost of Stamp paper will be borne by contractor

19. This enquiry is hoisted at website of MPPGCL and pasted on notice board of this office only.
20. **Maintenance period**:- 5 years of service guarantee to be provided at per SOR MPPWD w.e.f. 01/01/2024 item No. 22.23
21. The bidder shall insure that his firm has no pending obligation from this office otherwise his bid shall be disqualified.
22. **Security Deposit**:- Security deposit will be deducted from running bills of the work, @ 10% of bill amount, and such amount (10% of the value of work) will be released after successful completion of work.
23. **EMD**:- not applicable.
24. For amendment and further information, If any, please visit our web site www.mppgcl.mp.gov.in regularly. In case of any amendment and clarification, the responsibility lies with the bidders to collect the same from the web site of MPPGCL or office of undersigned before the last date. MPPGCL shall have no responsibility for any delay/omission on part of the bidder.

Please note, all rights are reserved with the undersigned to accept/reject any or all offers without assigning any reason, whatsoever it may be.

Encl:- Schedule & Price Bid.

Thanking you,


(B.K. Kushwaha)
Superintending Engineer (Civil)
Hydel Maint. & SI, MPPGCL Jabalpur

No.03-03-02/Enquiry -121/

Jabalpur/dated. / 02/2026

Copy to: (1) The ED (HR&A) MPPGCL, Rampur Jabalpur.

- (2) The Chief Engineer (M/M) MPPGCL Jabalpur.- Please hoist this enquiry on the Web Site of MPPGCL.
- (3) The Chief Engineer (Civil-Engg) MPPGCL Jabalpur
- (4) The E.E. (Civil) Hydel Maint.& SI, Dn. MPPGCL Jabalpur.
- (5) Notice Board.

(B.K. Kushwaha)
Superintending Engineer (Civil)
Hydel Maint. & SI, MPPGCL Jabalpur

SCHEDULE

Name of Work -Water proofing Treatment at Terrace for Central Training Insitute MPPGCL Nayagaon Jabalpur . Based on SOR MP PWD Building works w.e.f. 01/01/2024.

S.No.	SOR NO.	Particulars of item	Unit	Quantity
1	22.23	<p>Providing water proofing treatment over Roof, Wall, Chhajjas, Balcony with Rubberized elastomeric cold applied liquid waterproofing membrane blend of special resin and rubber with more than 1300% elongation (confirming ASTM-D2370-98), at leakage/seepage area consisting of the following operation.</p> <p>(i) Removal of damaged waterproofing treatment if any like bituminous membrane / plaster/ brick bat koba/screeding etc.</p> <p>(ii) Surface preparation: Roughening of surface by scrubbing with steel wire/ Nylon brush/ Removing all dust particles and washing with adequate water to clean completely, opening of cracks in 'V' groove in size of 5mm x 10m (WxD), filling of cracks with elastomeric creak filler/PU sealent repair of potholes and holor making on roof surface by polymer mortar with adding SBR bonding agent.</p> <p>(iii) Providing and applying 1st coating of rubberized elastomeric liquid membrane as primer (ratio 1:2 1 part liquid membrane and 2 part water) by brush/ Roller/ Spray having minimum thickness of 70-80 micron. Allow the coating to set in natural air for minimum 2 hrs, then put reinforcement by laying 45gsm fibre glass mesh and applying 2nd coat of rubberized elastomeric liquid membrane (Ratio: 1 part membrane and 20% water) with minimum thickness 100-120 micron. Allow the coating to set in natural air for minimum 12 hrs.</p> <p>(iv) Providing and applying 3rd coat of rubberized elastomeric liquid membrane (Ratio: 1 part membrane and 10% water). Total DFT (Dry film thickness) thickness after 3rd coat must be 280-300 micron and consumption in three coats @ 6.5kg for 10sqm.</p> <p>(v) Providing and applying 4th and 5th coat of High quality waterproof membrane in white colour, single component special synthetic resin based flexible thixotropic white color coating with excellent UV resistance (SRI - 144) with more than 300% elongation (confirming ASTM D 412-98) in ratio: 1 part membrane and 10% water thickness of 200 micron DFT in two coats, with average consumption @ 5kg per 10 sqm. After application of fourth coat let it air dry for minimum 3 hrs before application of fifth coat.</p> <p>(vi) The treated area must be tested for water leakage/seepage by flooding with water for 48 hrs.</p> <p>(vi) Application of membrane coating shall be got done by authorized applicator of manufacturer.</p> <p>(vii) 5 years of service guarantee to be provided. All above operations to be done in order as per direction on Engineer-in-Charge.</p>	Sqm	303.75
				Total

Seal & Signature of Bidder

No.03-03-02/Enquiry -121/ 242

Jabalpur/dated. 28/ 02/2026

PRICE BID

S.No.	Particulars of work	Offered Rate excluding GST
1	Water proofing Treatment at Terrace for Central training Institute MPPGCL, Nayagaon Jabalpur.	As par/ %..... Above/ %..... Below Besed on SOR MPPWD (Building works) w.e.f. 01/01/2024.

(Seal & Signature of Bidder)