

DUBRAJPUR PANCHAYAT SAMITI

DUBRAJPUR :: BIRBHUM

PIN - 731123 ; Tele-Fax: (03462) 244244 / 244221

E-Tender Notice

NIT NO - 15/DPS/2023

Memo No: **229/DPS/2023**


Date: **31.03.2023**

Percentage Rate Tender for the under mentioned works (annexure-I) are invited by the undersigned on behalf of Dubrajpur Panchayat Samiti from suitable eligible Contractors. The intending tenderer should download the detail Tender Notice along with tender document from "e-procurement" link under <http://wbttenders.gov.in> website. The tenderers will have to submit their bid on-line in two folder system containing pre qualification document, Technical Bid in one and Financial Bid in another.

1.	Tender Document download Starts date	31/03/2023	6.00 PM
2.	Tender Document download end date	08/04/2023	6.00 PM
3.	Online bid submission start	31/03/2023	6.00 PM
4.	Online bid submission end	08/04/2023	6.00 PM
5.	Time and Date opening Technical bid	10/04/2023	6.00 PM
8.	Time and Date opening Financial bid	Will be uploaded during Technical Evaluation	

Note:

- The detailed tender notice along with Tender Documents and other forms are available at <http://wbttenders.gov.in> website and notice is also available at website <http://birbhum.gov.in>
- The tenderer shall have to pay the EMD & Tender fees through online. The refund of the same as applicable through online procedure.
- All credentials must be supported with work order and completion certificate/payment certificate.**
- Irrelevant documents must not be uploaded. (This may cause disqualification in technical bid).
- All bidders must submit the Affidavit as per format enclosed with SBD.


Executive Officer
Dubrajpur Panchayat Samiti
Dubrajpur :: Birbhum

P.T.O.

DUBRAJPUR PANCHAYAT SAMITI

DUBRAJPUR :: BIRBHUM

PIN - 731123 : Tele-Fax: (03462) 244244 / 244221

Annexure-I E-Tender Notice NIT NO-15/DPS/2023


Memo No: 229 /DPS/2023

Date: 31.03.2023

SL No	Name of work	Location	Fund	Schedule Amount	Earnest Money	Participation Charge	Time of Completion
1.	construction of P.C.C. Road from Hazrapur Mukhagnitala to Chowrasta at Hazrapur in Parulia G.P.	Parulia G.P.	CSR	250000	5000	1000	30 days
2.	construction of Boundary wall with upgradation work at Gouranga Sayer Park beside Nepal Mazumder Savagriha under CSR fund of Bk.T.P.P, for the year 2022-23, within Dubrajpur Panchayet Samity	Block campus	CSR	200000	4000	1000	60 days
3.	Installation of T-Well with Submersible pump at Haridaspur in Gohaliara , under CSR fund of Bk.T.P.P, for the year 2022-23, within Dubrajpur Panchayet Samity	Gohaliara G.P	CSR	350000	7000	1000	45 days
4.	Installation of Solar Submersible pump with water spout at Gobindapur in Gohaliara G.P. under CSR Project of Bk.TPP ,WBPDCL of FY-2022-23	Gohaliara G.P	CSR	500000	10000	1000	45 days

The eligibility criteria are given below: -

- 1). The applicant in the same name and style as prime contractor should have successfully completed one contract of same nature of work at least 30% (Thirty Percent) value of the proposed contract within the last 5 years i.e. not before FY 2017-18. All relevant credential documents should be uploaded in Technical cover in a single pdf file as "Credential".
- 3). Copy of Income Tax return for the last 3 (three) financial year, Current Trade License, Updated Professional Tax clearance certificate, GST registration certificate & PAN Card should be uploaded in Technical cover in a single pdf file as "Technical" (Non-submission of above-mentioned documents will cause disqualification in technical bid)
- 4). In case of Electrical works the agency should have personnel having Electrical Contractors License & Supervisory License of respective category (1,2,7A,10 & 11)


Executive Officer
Dubrajpur Panchayat Samiti
Dubrajpur :: Birbhum

P.T.O.

DUBRAJPUR PANCHAYAT SAMITI

DUBRAJPUR :: BIRBHUM

PIN - 731123 ; Tele-Fax: (03462) 244244 / 244221


Memo No: 229 /1(16)/DPS/2023

Date: 31.03.2023

E-Tender Notice NIT NO -15/DPS/2023

Copy forwarded for information and necessary action to :

1. The Sabhadhipati, Birbhum Zilla Parishad.
2. The District Magistrate, Birbhum & Executive Officer, Birbhum Zilla Parishad.
3. The Additional District Magistrate, Birbhum & Additional Executive Officer, Birbhum Zilla Parishad.
4. The Sub Divisional Officer, Sadar (Suri) Sub-Division, Suri, Birbhum.
5. The District Planning Officer, Birbhum Zilla Parishad, Suri
6. The General Manager, Bk T.P.P.
7. The DIO, NIC, Birbhum with a request to publish the notice in Birbhum District's website <http://birbhum.gov.in>
8. The DICO, Birbhum with the request to publish the notice in a daily news paper and to send the bill to this end.
9. The Sabhapati, Dubrajpur Panchayat Samiti. He is requested to remain present with all members of "TENDER COMMITTEE" at the time of opening/evaluation of Technical Bid as well as opening/evaluation of Financial Bid.
10. The Karmadhyakshya of P.K.O.P.S.S. of this Panchayat Samiti.
- 11-13. All S.A.E., Dubrajpur Panchayat Samiti.
- 14-15. Technical Assistant (MGNREGA), of this block
16. Office Notice Board


Executive Officer
Dubrajpur Panchayat Samiti
Dubrajpur :: Birbhum


Schedule for Installation of T-Well with Submersible pump at Haridaspur in Gohalpara , under CSR fund of Bk.T.P.P. for the year 2022-23, within Dubrajpur Panchayet Samity

Sl. No.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
1	Labour for boring through any type of soil for sinking tube well of required dia. with top enlargement by rig boring system (either by reserve circulation or by direct rotary method) including hire charges and labour for rig machine, tools and plants, staging, force pumping set and making arrangement for water required for boring etc. complete and lowering of pipes, strainers, blind pipes etc. complete (b) For depth upto 250 metre for 150 mm dia. Tube well with top enlargement of 250 mm dia. (upto 50 metre).				
i)	(i) First 50 metre For 28 m from G.L.= For first 50 m i) 29m to 50 m	28.00	1,066.00	meter	29,848
ii)	Next 50 metre	22.00	746.20	meter	16,416
iii)	Next 21 metre	50.00	734.30	meter	36,715
		21.00	872.90	meter	18,331
2	Supply of PVC pipes & fittings Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). (A) PVC Pipes (Dia) ,200 mm	28.00	2,134.00	Metre	59,752
3	Supplying, fitting & fixing of 3 HP medini Submersible pump (Tilasker 3 Hp) with panelboard	1.00	28,000.00	Each set	28,000
4	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbow, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials, jointing materials, cutting pipes, making threads, cutting trenches upto 1.5 metre below surface in all sorts of soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) PVC Pipes (Dia) 50 mm	50	403.00	rm	20,150
5	Supplying, fitting & fixing of G.I. cap at top, 200 mm dia	1	669.00	Each set	669
6	Supplying, fitting & fixing of M.S. Clamp	1	350.00	Pair	350
7	Supplying, fitting & fixing of G.I. long bend 90 degree of 80 mm dia	1	200.00	nos	200
8	4. sqm mm cable (Fenolex) 3 crore	60	105.00	rm	6,300

Sl. No.	Description of items	Unit	A (meters)	B (meters)	C (meters)	Quantity	Total Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Each work is measurement of foundation excavation or drainage in all parts of soil (including method soil but excluding labour or substructure) including retaining, supporting or shoring the walls within a limit of 75 m in diameter. The item includes necessary retaining the sides of excavation, leveling, dressing and cementing the bottom, leveling and water in required completion.	Cu.M				4.275	4.275	Cu.M	119.27	522
2	Setting in foundation or joints by stone sand in layer not exceeding 100 mm in diameter and consolidating same by thorough saturation with water (ramming complete, including the cost of supply of sand (payment to be made on measurement of finished quantity). A) Do by fine sand B) Depth of excavation not exceeding 1500 mm.	Cu.M				1.775	1.775	Cu.M	572.95	1,016
3	Single level fine setting (80-100) of packed blower bricks including ramming and dressing bed to its proper level and filling joints with local sand.	Sq.M				4.000	4.000	Sq.M	266.00	1,064
4	Concrete concrete (6:3:1) with graded stone ballast (60 mm down stone chips) size excluding shuttering. A) In ground floor B) 5:3:1 proportion.	Cu.M				0.300	0.300	Cu.M	4,105.50	1,232
5	b) 25 mm to 30 mm thick wooden shuttering without strapping in foundation etc as per decision & direction of Engineer-in-Charge.	Sq.M				8.100	8.100	Sq.M	205.00	1,661
6	Bays and labour charges for shuttering with centering and necessary strapping up to 4 metre using approved steel props and thick hard wood planks of approved thickness with required sawing for concrete slab, beam, column, bench curved or straight including fitting, fixing and striking out after completion of works. (up to roof of ground floor)	Sq.M				17.710	17.710	Sq.M	328.00	5,809
7	Ordinary concrete concrete (mix 3:1.5:1) M 20 with graded stone chips (20 mm down excluding shuttering and reinforcement if any, in ground floor as per IS 456:2000. A) Plaster / Chandi variety.	Cu.M				3.445	3.445	Cu.M	4,976.83	17,145
8	Reinforcement for reinforced concrete work in the all parts of structures including distribution bars, stirrups, binders etc, including supply of rods, initial straightening and removal of loose rust (if necessary), cutting to required length, bending and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every inter section, complete as per drawing and direction. A) For works in foundation, basement and up to roof of ground floor / up to 4 metre.	M.T				0.297	0.297	M.T	54,682.67	16,241
9	Brick work with 1st class bricks in cement mortar (6:1). A) In foundation and plinth	Cu.M				0.394	0.394	Cu.M	4,198.04	1,651
10	125mm thick brick works with 1st class bricks in cement mortar (4:1)	Cu.M				16.485	16.485	Cu.M	584.50	9,635
11	Plaster with sand and cement mortar including rounding off or chamfering corners as directed and riding out joints or roughening of concrete surface, including chiselling, mulling and drip course where necessary (ground floor). (i) With 6:1 cement mortar B) 20 mm thick plaster, inside	Sq.M				18.054	18.054	Sq.M	149.74	2,703
12	c) 15 mm thick plaster, outside	Sq.M				28.846	28.846	Sq.M	132.54	3,823
13	With 4:1 cement mortar C) 10 mm thick plaster in ceiling etc.	Sq.M				6.485	6.485	Sq.M	119.54	775

216,731

Sl. No.	Description of Items	Nos.	L (metre)	B (metre)	H (metre)	Quantity	Total Quantity	Unit	Rate (Rs.)	Amount (Rs.)
14	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothing surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : with a coat of primer (a) on steel surface (iv) Two coats (with any shade except white)						6.453	sqm	108.00	697
15	(a) M.S. or W.I. Ornamental grill of approved design joints continuously welded with M.S. W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in G.F. (i) Grill weighing 16 kg. Sq M. @ 14kg/ sqm b) Supplying, fitting and fixing steel windows.....						11.340	Kg	98.88	1,121
16	Applying decorative cement based paint of approved quality after preparing the surface including scraping the same thoroughly (plastered or concrete surface) as per manufacturer's specification in ground floor one coats.						53.384	sqm	49.00	2,616
17	Operable steel window						0.810	sqm	2,640.00	2,138
18	M.S. gate of jail type as per approved design made of strong M.S. frame work, intermediate stiffeners and round / square bars or angles. M.S. sheet (not less than 14 gauge) gussets, cleats etc. including necessary riveting, bolting, welding, locking and hanging arrangements, fitting and fixing complete as per direction of the Engineer-in-charge @ 25kg/sqm						43.875	sqm	101.91	4,471
19	Net cement punning						11.030	sqm	32.74	361
20	Artificial stone in floor, dado, staircase, etc. with cement concrete (4:2:1) with stone chips laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (2:1) including smooth finishing and rounding off corners and including application of cement slurry before flooring works, using cement @ 1.75kg / sqm all complete including all materials and labours in ground floor - 25mm thick						5.000	sqm	240.02	1,200
21	Making signboard by block letter or digit painting (size 7cm)									
Sub - Total (G.F. Construction Work only)							1,000			1,030
Gross total=										293,674
Add for CGST & SGST 18%=										293,674
Total=										52,861
Add for labour welfare cess@1%=										346,535
Total=										3,465
										350,000


Executive Officer
 Durbajpur Panchayat Samiti
 Durbajpur, Birkhum